



09/02/2025

4003-QA #16 Mineral Filler

Procedure	Sieve/Test	Average	Unit	QA #16 Mineral Filler
	#8 (2.36mm)	100.0	%	100-100
	#16 (1.18mm)	100.0	%	100-100
	#30 (.6mm)	100.0	%	100-100
	#60 (.25mm)	99.9	%	
	#80 (.18mm)	99.3	%	
	#100 (.15mm)	98.4	%	96-100
	#140 (.106mm)	94.3	%	80-100
	#200 (75μm)	87.2	%	70-100
	#325 (45μm)	80.4	%	25-100
	Al2O3	0.09	%	
	CaCO3	95.81	%	
	Calcium (Ca)	38.38	%	
	Fe2O3	0.19	%	
	Magnesium (Mg)	0.60	%	
	MgCO3	2.14	%	
	SiO2	0.74	%	0.00-4.00

This report certifies tickets issued to the listed customer for 24 hours after 6:00AM EST of the date published. If the COA was issued on a Saturday, it certifies tickets until Tuesday at 5:59AM EST. (If a Monday holiday, COA issued Saturday certifies until Wednesday at 5:59AM EST)

Name/Title

Laresa Ingram / QC Manager