



Princeton Quarry  
10234 Hopkinsville Rd  
Princeton, KY 42445  
270-365-9524

05/04/2026

### 4003-Resin Material

Procedure	Sieve/Test	Average	Unit	Resin Material
	#4 (4.75mm)	100.0	%	
	#8 (2.36mm)	100.0	%	
	#20 (.85mm)	99.2	%	
	#30 (.6mm)	96.6	%	93-99
	#50 (.3mm)	82.7	%	80-90
	#100 (.15mm)	62.0	%	58-76
	#200 (75µm)	49.00	%	38-61
	#325 (45µm)	41.36	%	34-46
	Al2O3	0.59	%	≤3.00
	CaCO3	95.38	%	≥90.00
	Fe2O3	0.10	%	≤3.00
	MgCO3	1.78	%	
	RNV	1.6		
	SiO2	1.65	%	≤3.00

Name/Title

Laresa Ingram / QC Manager