



Princeton Quarry  
10234 Hopkinsville Rd  
Princeton, KY 42445  
270-365-9524

06/01/2026

### 4003-Resin Material

Procedure	Sieve/Test	Average	Unit	Resin Material
	#4 (4.75mm)	100.0	%	
	#8 (2.36mm)	100.0	%	
	#20 (.85mm)	99.2	%	
	#30 (.6mm)	96.6	%	93-99
	#50 (.3mm)	82.7	%	80-90
	#100 (.15mm)	62.2	%	58-76
	#200 (75µm)	49.02	%	38-61
	#325 (45µm)	41.26	%	34-46
	Al <sub>2</sub> O <sub>3</sub>	0.60	%	≤3.00
	CaCO <sub>3</sub>	95.36	%	≥90.00
	Fe <sub>2</sub> O <sub>3</sub>	0.10	%	≤3.00
	MgCO <sub>3</sub>	1.82	%	
	SiO <sub>2</sub>	1.65	%	≤3.00
	Grad Loss	0.000	%	
	Total Moisture	0.04	%	0.00-0.50

Name/Title

Laresa Ingram / QC Manager